	Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
64	2.56	KSRB 4.2.1: Providing and laying in position reinforced cement concrete of design I mix M25 with with OPC Cement @340 kgs with 20mm and down size graded granite metal coars aggregates @0.70 cum and fine aggregates @ 0.47cum with superplasticisers @3liters confirming to IS9103-1999 Reaffirmed -2008 at machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation for footings , pedestals , retaining walls ,return walls ,walls(any thickness) including attached pilasters, columns , pillars, posts , struts, buttresses, bed blocks,, anchor blocks & plinth etc.including cost of all materials, labour, HOM of machinary, curing complete as per specifications. Specification No. KBS-4.1,4.6 Specification No. KBS4.1,4.6 (PWD, S.R. 2016-17)(Page No. 13, Item No.4.10)	Cum	6718.68	Rupees Six Thousand Seven Hundred Eighteen And Paise Sixty Eight Only
65	2.56	KSRB 4-4.1 Extra for use of water proofing compound in Cement concrete of mix 1:1:2, at one kg of compound per bag of cement. (PWD, S.R. 2016-17)(Page No. 14, Item No.4.24)	Cum	275.4	Rupees Two Hundred Seventy Five And Paise Forty Only
66	9.60	KSRB 4-6.7: Providing and removing centering, shuttering, strutting, propping etc., and removal of from work for sides and soffits of beams, beam haunchings, cantilever griders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (PWD, S.R. 2016-17) (Page No. 16, Item No.4.34)	Sqm	276.48	Rupees Two Hundred Seventy Six And Paise Forty Eight Only
67	9.00	KSRB 4-6.2: Providing and removing centering, shuttering, strutting, propping etc., and removal of from work for flat surface such as suspended floors, roofs landings, balconies and likes, thickness upto 200mm including cost of all materials, labour complete as per specificationSpecification No. KBS 4.6.2 - 0-5.0mts Ht (PWD, S.R. 2016-17)(Page No. 15, Item No.4.29.2)	Sqm	594	Rupees Five Hundred Ninety Four Only
68	13.92	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/cum having a minimum average compressive strength of 4.00N/mm2 confirming to IS 2185(Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding , curing , hire charges of machineries etc., complete as per specfications . KBS No.5.4 with solid concrete blocks of size 40x20x20cm (PWD, S.R. 2016-17) (Page No. 24, item No. 5.26.1)	Sqm	1011.96	Rupees One Thousand Eleven And Paise Ninety Six Only
69	0.27	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 -do- TMT bars Fe 500 (PWD, S.R. 2016-17)(Page No. 1, item No. 4.46.2)	T	76329	Rupees Seventy Six Thousand Three Hundred Twenty Nine Only
70	8.69	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. specification. No. KBS 2.9 (PWD, S.R. 2016-17)(Page No. 6, item No. 2.10)	Cum	137.16	Rupees One Hundred Thirty Seven And Paise Sixteen Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BDMP DIVISION
BENGALURU-560 010

	Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
71	21.60	KSRB 15-3.10: Providing 20 mm thick cement plaster in single coat with CM 1:3 to stone masonry / concrete surface including rounding off corners wherever required smooth rendering: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specification (PWD, S.R. 2016-17)(Page No. 114, item No. 15.18)	Sqm	279.72	Rupees Two Hundred Seventy Nine And Paise Seventy Two Only
72	7.48	KSRB 15-3.13: Providing 12mm thick cement plastering in single coat with cement mortar 1:3 to ceiling l including rounding off corners wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specification. (PWD, S.R. 2016-17)(Page No. 114, item No. 15.21)	Sqm	192.24	Rupees One Hundred Ninety Two And Paise Twenty Four Only
73	0.36	Providing and fixing MS door for sump including cost of labour, materials and one coat of primer paint and two coats of enamel painting etc, as directed by the engineer in charge of work (PWD, S.R. 2016-17)	Sqm	3780	Rupees Three Thousand Seven Hundred Eighty Only
74	130.00	Open Conduit System Supplying heavy gauge PVC conduit pipe .....dia ..... mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.(Page No. 2, Item No.1.1.1 & 1.1.2) **19/20mm dia 2mm thick**	m	54	Rupees Fifty Four Only
75	110.00	Open Conduit System Supplying heavy gauge PVC conduit pipe .....dia ..... mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.(Page No. 2, Item No.1.1.1 & 1.1.2) **25mm dia 2mm thick**	m	70	Rupees Seventy Only
76	20.00	Concealed Conduit System: Supplying heavy guage PVC conduit pipe ...mm dia ...mm thick confirmingto IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary.(Page No. 2, Item No.1.2.1 & 1.2.2) **19/20mm dia 2mm thick**	m	43	Rupees Forty Three Only
77	15.00	Concealed Conduit System: Supplying heavy guage PVC conduit pipe ...mm dia ...mm thick confirmingto IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary.(Page No. 2, Item No.1.2.1 & 1.2.2) **25mm dia 2mm thick**	m	57	Rupees Fifty Seven Only
78	60.00	Groove Cutting : Supplying heavy guage PVC conduit pipe ...mm dia ...mm thick with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, by groove cutting in wall and fixing by using U or J hooks and cement plastering up to the wall surface and run with 18SWG GI fish wire through out the conduit where ever necessary.(Page No. 2, Item No.1.3.1 & 1.3.2) **19/20mm dia 2mm thick**	m	56	Rupees Fifty Six Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
79	40.00	Groove Cutting : Supplying heavy guage PVC conduit pipe ...mm dia ...mm thick with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, by groove cutting in wall and fixing by using U or J hooks and cement plastering up to the wall surface and run with 18SWG GI fish wire through out the conduit where ever necessary.(Page No. 2, Item No.1.3.1 & 1.3.2) **25mm dia 2mm thick**	m	58	Rupees Fifty Eight Only
80	25.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall(Page No. 15, Item No.3.5.1 to 3.5.5) **1-3Way**	Each	91	Rupees Ninety One Only
81	20.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall(Page No. 15, Item No.3.5.1 to 3.5.5) **4-5Way**	Each	98	Rupees Ninety Eight Only
82	5.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall(Page No. 15, Item No.3.5.1 to 3.5.5) **6 Way**	Each	121	Rupees One Hundred Twenty One Only
83	15.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall(Page No. 15, Item No.3.5.1 to 3.5.5) 8Way	Each	140	Rupees One Hundred Forty Only
84	10.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall(Page No. 15, Item No.3.5.1 to 3.5.5)10-12Way	Each	159	Rupees One Hundred Fifty Nine Only
85	25.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(Page No. 16, Item No.3.6.1 to 3.6.5) 1-3Way	Each	109	Rupees One Hundred Nine Only
86	20.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(Page No. 16, Item No.3.6.1 to 3.6.5) 4-5Way	Each	122	Rupees One Hundred Twenty Two Only
87	5.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(Page No. 16, Item No.3.6.1 to 3.6.5) 6 Way	Each	173	Rupees One Hundred Seventy Three Only
88	15.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(Page No. 16, Item No.3.6.1 to 3.6.5) 8 Way	Each	200	Rupees Two Hundred Only
89	10.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.(Page No. 16, Item No.3.6.1 to 3.6.5) 10-12Way	Each	267	Rupees Two Hundred Sixty Seven Only
90	52.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. (Page No. 16, Item No.3.7) 6 Amps one way	Each	63	Rupees Sixty Three Only
91	4.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. (Page No. 16, Item No.3.7) 6Amps 3way socket	Each	95	Rupees Ninety Five Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
92	10.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. (Page No. 16, Item No.3.7) Stepped Fan Regulator	Each	286	Rupees Two Hundred Eighty Six Only
93	6.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. (Page No. 16, Item No.3.7) 16Amps one way switch	Each	114	Rupees One Hundred Fourteen Only
94	6.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. (Page No. 16, Item No.3.7) 6/16Amps universal socket	Each	147	Rupees One Hundred Forty Seven Only
95	1.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293. (Page No. 16, Item No.3.7) TV/Telephone socket	Each	82	Rupees Eighty Two Only
96	12.00	supplying and wiring adopting loop system in existing PVC conduit / casing capping using 1100 v grade , copper conductor flexible multistrand FRLS PVC insulated, 2 x1.5sq.mm cable confirming to the GTP, without switch, the other end of the wires shall be terminated with sufficient loose length in a wood /PVC cound block. complete for each outlet. (Page No. 5, Item No.2.3.1 to 2.3.5) Short point up to 3Mtr from tapping point to out let via switch box	Each	144	Rupees One Hundred Forty Four Only
97	40.00	supplying and wiring adopting loop system in existing PVC conduit / casing capping using 1100 v grade , copper conductor flexible multistrand FRLS PVC insulated, 2 x1.5sq.mm cable confirming to the GTP, without switch, the other end of the wires shall be terminated with sufficient loose length in a wood /PVC cound block. complete for each outlet. (Page No. 5, Item No.2.3.1 to 2.3.5) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box	Each	215	Rupees Two Hundred Fifteen Only
98	12.00	supplying and wiring adopting loop system in existing PVC conduit / casing capping using 1100 v grade , copper conductor flexible multistrand FRLS PVC insulated, 2 x1.5sq.mm cable confirming to the GTP, without switch, the other end of the wires shall be terminated with sufficient loose length in a wood /PVC cound block. complete for each outlet. (Page No. 5, Item No.2.3.1 to 2.3.5) Long point above 6Mtr up to 10Mtr from tapping point to out let via switch box	Each	334	Rupees Three Hundred Thirty Four Only
99	5.00	supplying and wiring adopting loop system in existing PVC conduit / casing capping using 1100 v grade , copper conductor flexible multistrand FRLS PVC insulated, 2 x1.5sq.mm cable confirming to the GTP, without switch, the other end of the wires shall be terminated with sufficient loose length in a wood /PVC cound block. complete for each outlet. (Page No. 5, Item No.2.3.1 to 2.3.5) Two Outlet in a row, above 3.0M unto 6.0M from tapping point to outlet via switch box.	Each	423	Rupees Four Hundred Twenty Three Only
100	2.00	supplying and wiring adopting loop system in existing PVC conduit / casing capping using 1100 v grade , copper conductor flexible multistrand FRLS PVC insulated, 2 x1.5sq.mm cable confirming to the GTP, without switch, the other end of the wires shall be terminated with sufficient loose length in a wood /PVC cound block. complete for each outlet. (Page No. 5, Item No.2.3.1 to 2.3.5) Three Outlet in a row, above 6.0M unto 10.0M from tapping point to outlet via switch box.	Each	593	Rupees Five Hundred Ninety Three Only
101	12.00	Supplying and fixing metal Fan box with Round Hook. (Page No. 3, Item No. 1.12)	Each	92	Rupees Ninety Two Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP DIVISION
BENGALURU-560 010

	Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
102	200.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper with low conductor resistance single core cable in open or concealed system of wiring with specified IS-694:1990 & comfirming to GTP of Group-A .(Page No. 6, Item No.2.5.2 to 2.5.6) 1.5 sqmm	m	18.6	Rupees Eighteen And Paise Sixty Only
103	350.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper with low conductor resistance single core cable in open or concealed system of wiring with specified IS-694:1990 & comfirming to GTP of Group-A .(Page No. 6, Item No.2.5.2 to 2.5.6) 2.5 sqmm	m	29.2	Rupees Twenty Nine And Paise Twenty Only
104	120.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper with low conductor resistance single core cable in open or concealed system of wiring with specified IS-694:1990 & comfirming to GTP of Group-A .(Page No. 6, Item No.2.5.2 to 2.5.6) 25mm dia 2mm thick	m	42.1	Rupees Forty Two And Paise Ten Only
105	50.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper with low conductor resistance single core cable in open or concealed system of wiring with specified IS-694:1990 & comfirming to GTP of Group-A .(Page No. 6, Item No.2.5.2 to 2.5.6) 6 sqmm	m	63.8	Rupees Sixty Three And Paise Eighty Only
106	20.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper with low conductor resistance single core cable in open or concealed system of wiring with specified IS-694:1990 & comfirming to GTP of Group-A .(Page No. 6, Item No.2.5.2 to 2.5.6) 10 sqmm	m	108	Rupees One Hundred Eight Only
107	1.00	Supplying and fixing regular MCB distribution boards on wall/wood board/flush mountin using required clamps, bolts, nuts with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with powder coated painting. Made out of 14 SWG M.S enclosure.(Page No. 47, Item No.6.17.7, 6.17.8, 6.17.6) Double door 4 way TP & N	m	2399	Rupees Two Thousand Three Hundred Ninety Nine Only
108	1.00	Supplying and fixing regular MCB distribution boards on wall/wood board/flush mountin using required clamps, bolts, nuts with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with powder coated painting. Made out of 14 SWG M.S enclosure.(Page No. 47, Item No.6.17.7, 6.17.8, 6.17.6) Double door 6 way TP & N	m	2867	Rupees Two Thousand Eight Hundred Sixty Seven Only
109	1.00	Supplying and fixing regular MCB distribution boards on wall/wood board/flush mountin using required clamps, bolts, nuts with provision for fixing suitable type capacity MCB's single phase/3 phase/single door with powder coated painting. Made out of 14 SWG M.S enclosure.(Page No. 47, Item No.6.17.7, 6.17.8, 6.17.6) Double door 12 way SP & N	m	1622	Rupees One Thousand Six Hundred Twenty Two Only
110	10.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898 (Page No. 47, Item No. 6.16.1, 6.16.6, 6.16.5)) 5-32Amps SP	Each	418	Rupees Four Hundred Eighteen Only
111	2.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898 (Page No. 47, Item No. 6.16.1, 6.16.6, 6.16.5)) 5-32Amps TPN	Each	1547	Rupees One Thousand Five Hundred Forty Seven Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone

Contractor

	Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
	2.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898 (Page No. 47, Item No. 6.16.1, 6.16.6, 6.16.5)) 40-63Amps TPN	Each	1936	Rupees One Thousand Nine Hundred Thirty Six Only
113	1.00	Supplying, fixing and wiring eaarth Earth Leakage Miniature Circuit Breaker [ELMCB] 240/250V upto 300mA sensitivity on existing wood/panel board.(Page No. 47, Item No. 6.18.1 & 6.18.4) 16-25Amps 2Pole	Each	2412	Rupees Two Thousand Four Hundred Twelve Only
114	1.00	Supplying, fixing and wiring eaarth Earth Leakage Miniature Circuit Breaker [ELMCB] 240/250V upto 300mA sensitivity on existing wood/panel board.(Page No. 47, Item No. 6.18.1 & 6.18.4) 32-40Amps 4Pole	Each	3350	Rupees Three Thousand Three Hundred Fifty Only
115	8500.00	Fabricating supplying and mounting MS box made out ...SWG suitable for floor I wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete (Page No. 49, Item No. 6.40.1)	Each	0.37	Rupees And Paise Thirty Seven Only
116	1.00	Supplying .....amps rated 3phase with neutral bus bar using required capacity electrolytic aluminum strips covered with heat shrinkable coloured PVC sleeve, mounted on phenoliciFRP/DMC insulator which are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete. (Page No. 49, Item No. 6.38.1)	Each	2135	Rupees Two Thousand One Hundred Thirty Five Only
117	3.00	Supplying fixing angle iron frame work fabricated out of M.S angle iron .. And m.S flat.... With bolts, washers etc., and painted with two coats of red oxide and then two coats of approved paint. (Page No. 49, Item No. 6.39.1 & 6.39.4) 40x40x6 mm	Each	263	Rupees Two Hundred Sixty Three Only
118	3.00	Supplying fixing angle iron frame work fabricated out of M.S angle iron .. And m.S flat.... With bolts, washers etc., and painted with two coats of red oxide and then two coats of approved paint. (Page No. 49, Item No. 6.39.1 & 6.39.4) 50x100x50x6 mm	Each	648	Rupees Six Hundred Forty Eight Only
119	1.00	Supplying and fixing Moulded Case Circuit Breaker (MCCB) .over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of Overload and Short circuit with thermal Magnetic/Micro processor release and Earth Fault as per IS-13947. (Ieu= Ics) (Page No. 46, Item No. 6.13.6)	Each	5809	Rupees Five Thousand Eight Hundred Nine Only
120	1.00	Supplying of multi function degital meter with three line backlight LCD type display for voltage , current frequency, power, power factor, KVA, KWH,KVAR suitable for 3 phase, 4 wire LT network with IP 54degree of protection and completely wired as required with communication port and class 0.5s accuracy. (Page No. 48, Item No. 6.31)	Each	8003	Rupees Eight Thousand Three Only
121	1.00	Supplying, fixing and wiring 0 to 600Volts 96x96mm AC Voltmeter on existing panel/wood board. (Page No. 48, Item No. 6.20)	Each	390	Rupees Three Hundred Ninety Only
122	1.00	Supplying, fixing and wiring 50/5 to 400/5Amps 5VA burden Current Transformer. Class 0.5 accuracy with Tape Wound (Page No. 48, Item No. 6.32)	Each	483	Rupees Four Hundred Eighty Three Only
123	3.00	Supplying and fixing of LED type panel board indicating lamp with required colour suitable for 220v A.C. 50 Hz 12/24v D.C (Page No. 48, Item No. 6.36)	Each	442	Rupees Four Hundred Forty Two Only

Executive Engineer
Project Division 2
Yelahanka Zone

Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

		Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
	1.00	Supplying of on load change over switches 4 poles, AC-23A Duty, 415V, 50Hz, AC Supply. (Page No. 45, Item No. 6.11.2) 100-125Amps	Each	6426	Rupees Six Thousand Four Hundred Twenty Six Only
125	18.00	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No.of Strip indicated in GTP & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A (Page No. 55, Item No. 7.4.7 7.4.4) 3.5 core 50 sqmm	Each	265	Rupees Two Hundred Sixty Five Only
126	25.00	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No.of Strip indicated in GTP & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A (Page No. 55, Item No. 7.4.7 7.4.4) 4 core 16 sqmm	Each	140.4	Rupees One Hundred Forty And Paise Forty Only
127	30.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.(Page No. 61, Item No. 7.8.1 & 7.8.2) 25 sqmm to 75 sqmm	Each	16.2	Rupees Sixteen And Paise Twenty Only
128	50.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.(Page No. 61, Item No. 7.8.1 & 7.8.2) 6 sqmm 16 Sqmm	Each	10.8	Rupees Ten And Paise Eighty Only
129	48.00	Digging of trench of 0.6m deep x 0.50 mtr wide refiling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7)(Page No. 61, Item No. 7.9.1) In soil (ordinary)	Each	78	Rupees Seventy Eight Only
130	48.00	providing and filling sand in exvated trench to cover already laid UG cable to a depth of 150mm alround the cable.(Page No. 62, Item No. 7.10)	Each	103	Rupees One Hundred Three Only
131	28.00	providing and laying in position 100mm dia stone ware pipe in existing trench (Page No. 62, Item No. 7.11)	Each	223	Rupees Two Hundred Twenty Three Only
132	15.00	Supplying and fixing of class A (medium duty) GI pipe of wall thick ness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class.(Page No. 62, Item No. 7.12.3) 65 mm	Each	585	Rupees Five Hundred Eighty Five Only
133	1.00	Supplying and fixing L.T cast iron pot heads suitable for 1.1 Kv class UG cable filled with necessory bitumin / insulating compound Complete with terminals, clamps, bolts, nuts and washers.(Page No. 62, Item No. 7.13.5)	Each	637	Rupees Six Hundred Thirty Seven Only
134	2.00	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only)(Page No. 62, Item No. 7.14.6) 63mm dia	Each	400	Rupees Four Hundred Only
135	12.00	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only)(Page No. 62, Item No. 7.14.6) 50 sqmm Long Barrel	Each	62.4	Rupees Sixty Two And Paise Forty Only
136	12.00	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only)(Page No. 62, Item No. 7.14.6) 6 sqmm	Each	6.25	Rupees Six And Paise Twenty Five Only
137	4.00	Supplying fixing and wiring earth electrode for grounding of lifts, transformers, DG sets etc using 40mm dia 2.9mm thick 2.5 mtr long GI pipe with GI funnel with mesh and suitable size reducer fixed on the top of the earth electrode. The funnel should be enclosed in a CC chamber of 400x400x400mm with a cast iron cover. The earth electrode shall have staggered holes of 12mm dia and the electrode should be covered 150mm alround with alternate layers of salt and charcoal from the bottom of the CC chamber. The connection from the electrode is to be established through GI strip using GI bolts and nuts. (Page No. 55, Item No. 7.2)	Each	4317	Rupees Four Thousand Three Hundred Seventeen Only

Executive Engineer
Project Division
Yelahanka Zone

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor

	Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
138	50.00	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. (Page No. 55, Item No. 7.3.2) GI strip 25x6mm	m	118	Rupees One Hundred Eighteen Only
139	8.00	Supplying of 2' feet - LED PVC Square Batten ..W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50Hz & Power factor >0.9 along with CE approved drivers. 5 years Warranty against any manufacturing defect working under standard electrical condition (Page No. 25, Item No. 4.29.2) LED light fighting 4' - 28 watts	Each	1774	Rupees One Thousand Seven Hundred Seventy Four Only
140	12.00	Supplying and fixing PBBC/Bakelite straight or slant batten holder and wiring with 60w/230 volts lamp. (Page No. 20, Item No. 4.2)	Each	183	Rupees One Hundred Eighty Three Only
141	10.00	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system. (Page No. 78, Item No. 9.3.2.1) 56" Sweep (1400mm) Regular moduel	Each	2418	Rupees Two Thousand Four Hundred Eighteen Only
142	2.00	Supplying exhaust fan of 1440 RPM of 300mm (12") sizewith bracket blades complete for light duty suitable to operate on 230V 50Hz. AC Supply (Page No. 78, Item No. 9.1)	Each	1700	Rupees One Thousand Seven Hundred Only
143	16.00	Fixing all types and all capacities fluorescent / false ceiling/spotlight/ CFLfittings indoor on the wall/ ceiling/rafters / girders using 23/0.0076" twin twisted RVC insulated wires, required nos of round blocks and clamps (if required) (Page No. 78, Item No. 9.1)	Each	98	Rupees Ninety Eight Only
144	16.00	Fixing fluorescent light using 2mtr long 19mm 18 SWG enameled braised conduit of two Nos. rod pendent with ball socket with check nuts all nickel plated (Page No. 109, Item No. 17.7.4)	Each	504	Rupees Five Hundred Four Only
145	10.00	Fixing a ceiling /Wall mounting fan of all capacities and all types to the existing 'S' hook with fan regulator to the existing board together with supplying and fixing 5 amps.ceiling rose,necessary length of 23/0.0076 inch PVC insulated twin twisted copper wire of approved quality, mounted on a suitable aize wooden board and wired(Page No. 109, Item No. 17.9)	Each	237	Rupees Two Hundred Thirty Seven Only
146	10.00	Fixing a ceiling fan with extra length of GI pipe of class B 19mm dia for down rod(Page No. 109, Item No. 17.10)	Each	164	Rupees One Hundred Sixty Four Only
147	6.00	Fixing one Exhast fan in the nitch already left in the wall with bolts and nets and 5 amps. Ceiling rose with sufficient length of 23 / 0.0076 inch PVC insulated twin core wire. (Page No. 109, Item No. 17.12)	Each	412	Rupees Four Hundred Twelve Only

20/4/18

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor

Exective Engineer
Project Division
Yelahanka Zone